



TT#

## TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



CUSTOMER	FYF-LLC	PO#	Final - per Ryan Schultz - 7/17
ATTN:	Ryan Schultz	DATE	7/18/2017
ADDRESS	43 South Water St East Fort Atkinson, WI 53538	ح	The Downtowner
PHONE	773-425-6456	JOB LOCATION. ¿	640 West Main Street, Lake Geneva, WI 53147
FAX	_	SHIP MODE <u>I</u> QUOTE	FOB LAKE GENEVA, WI  X  ORDER

TOTAL WEIGHT THIS PAGE

ITEM PRICE CODE QTY **DESCRIPTION** RR/FG WEIGHT **EACH TOTAL** basement - stair stringers 4169PB 2 3.125 in. x 12.375 in. DF, 24F-1.8E 454 \$836.76 **EXT** \$418.38 1st fl - stairs (top of basement stair & bottom of 1st fl stair.) 449PBN 3.125 in. x 12.375 in. DF, 24F-1.8E \$231.60 2 EXT 144 \$115.80 1st floor - stair stringers 4199PB 2 3.125 in. x 12.375 in. DF, 24F-1.8E EXT 540 \$487.64 \$975.28 1st floor - along GL E (3-4) & (1-2) & along GL D (2-3) 6189PB 18' 5.125 in. x 12.375 in. DF, 24F-1.8E **EXT** 804 \$512.30 \$1,536.91 3 1st floor - along GL E (2-3) 6199PB 5.125 in. x 12.375 in. DF, 24F-1.8E EXT 283 \$540.76 \$540.76 1st floor - girt-E 655PBM 6' 5.125 in. x 6.875 in. DF, 24F-1.8E 41 \$116.05 INT \$116.05 1st floor - girt-SE 685PBM 8' 5.125 in. x 6.875 in. DF, 24F-1.8E INT 66 \$128.95 \$128.95 1 1st floor - girt-NE 6105PB 92 11' 5.125 in. x 6.875 in. DF, 24F-1.8E INT \$177.30 \$177.30 1st floor - girt-E 6155PB 15' 5.125 in. x 6.875 in. DF, 24F-1.8E 124 1 INT \$241.79 \$241.79 16' 5.125 in. x 6.875 in. DF, 24F-1.8E 248 1st floor - girt-N & S 6155PB 2 INT \$257.91 \$515.82 1st floor - along 5 (B-E) 8229PB 6.75 in. x 12.375 in. DF, 24F-1.8e 467 \$776.47 \$776.47 **EXT** 1 2nd Floor - top of 1st floor stair 4411PB 3.125 in. x 15.125 in. DF, 24F-1.8e 46 1 EXT \$111.81 \$111.81 2nd Floor - along E (1-2) 41511PF 3.125 in. x 15.125 in. DF, 24F-1.8e \$419.30 186 **EXT** \$419.30 2nd Floor - along E (3-5) & along D (2-3) 41711PH 3.125 in. x 15.125 in. DF, 24F-1.8e 394 \$952.95 2 **EXT** \$476.48 220 2nd Floor - along E (2-3) 41911PE 3.125 in. x 15.125 in. DF, 24F-1.8e \$531.11 **EXT** \$531.11 Roof - along E (1-2) 41513PE 3.125 in. x 17.875 in. DF, 24F-1.8e 1 **EXT** 205 \$491.16 \$491.16 Roof - along E (3-5) 41713PE 3.125 in. x 17.875 in. DF, 24F-1.8e EXT 233 \$589.39 \$589.39 1 Roof - along E (2-3) 41913PE 3.125 in. x 17.875 in. DF, 24F-1.8e \$622.13 19' EXT 260 1 \$622.13 Roof - along 1 (B-E) 42713PE 3.125 in. x 17.875 in. DF, 24F-1.8e \$884.08 **EXT** 370 \$884.08 2nd - along C (1-2) 61511PF 15' 5.125 in. x 15.125 in. DF, 24F-1.8e 273 \$514.49 **EXT** \$514.49 18' 5.125 in. x 15.125 in. DF, 24F-1.8e 2nd - along C (2-3) & (3-5) 61711PH EXT 618 \$617.39 \$1,234.77 Chad Kragness

PAGE 1 OF 3

QUOTE GOOD FOR 10 DAYS.

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at time of order, balance upon delivery (unless negotiated otherwise)

SUBTOTAL THIS PAGE PPROVE

6,068

\$12,428.88

07/18/2017



## TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



Final - per Ryan Schultz - 7/17 PO# CUSTOMER FYF-LLC ATTN: DATE 7/18/2017 Ryan Schultz **ADDRESS** 43 South Water St. East JOB NAME The Downtowner Fort Atkinson, WI 53538 640 West Main Street, Lake Geneva, WI 53147 JOB LOCATION: PHONE 773-425-6456 SHIP MODE FOB LAKE GENEVA, WI FAX QUOTE <u>X</u> ORDER TT# PAGE 2 OF 3

	ITEM CODE	QTY	DESCRIPTION	RR/FG	WEIGHT	PRICE EACH	TOTAL
Doof slang 2 (D.E.)	(2010DF	•			10.5		<b>\$200.51</b>
Roof - along 3 (B-E)		1	24' 5.125 in. x 17.875 in. DF, 24F-1.8E	EXT	495	\$988.51	\$988.51
Roof - along 2 (B-E)	62513PE	1	25' 5.125 in. x 17.875 in. DF, 24F-1.8E	EXT	538	\$1,029.70	\$1,029.70
2nd - along 5 (B-E)	82211PF	<u>.</u> 1	23' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	271	\$959.00	\$959.00
Zrid - alorig 5 (B-E)	0221111		23 0.73 m. x 13.123 m. D1 , 241 1.0L	LXI	2/1	ψ555.00	Ψ/3/.00
2nd - along 2 (B-E) & along 3 (B-E)	82511PE	2	26' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	1,240	\$1,084.10	\$2,168.20
2nd - along 1 (B-E)	83011PE	1	30' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	744	\$1,250.89	\$1,250.89
roof - along 5 (B-E)	82213PE	1	23' 6.75 in. x 17.875 in. DF, 24F-1.8E	EXT	675	\$1,117.40	\$1,117.40
roof - along B (1-2)		1	15' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	189	\$414.88	\$414.88
roof - along B (3-5)		1	18' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	215	\$497.87	\$497.87
roof - along B (2-3)	41912PE	11	19' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	240	\$525.53	\$525.53
roof - along C (3-5)		11	22' 5.125 in. x 13.75 in. DF, 24F-1.8E	EXT	363	\$706.16	\$706.16
roof - along C (1-2)		1	15' 5.125 in. x 13.75 in. DF, 24F-1.8E	INT	248	\$414.26	\$414.26
roof - along C (2-3)	61910PE	1	19' 5.125 in. x 13.75 in. DF, 24F-1.8E	INT	314	\$524.73	\$524.73
	<=====================================	•				2	420101
basement - columns at (E-2), (E-2), (E-3)		3	8' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	174	\$128.95	\$386.86
basement - columns at D-2 & D-3		2	17' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	280	\$274.03	\$548.06
basement - columns at D-1	695PBM	1	18' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	150	\$290.15	\$290.15
1et column (P.1) (P.2) (P.2)	675DD14		01.5.105; C.075; DE 04E 1.0E		17.4	<b>0</b> 440.0=	Ф220 02
1st - column (B-1), (B-2), (B-3)		3	8' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	174	\$113.27	\$339.82
1st - column (B-3)		1	9' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	74	\$127.44	\$127.44
	6105PBI	7	10' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	581	\$141.57	\$990.98
2nd - column (C-5)	6105PBI	7	11' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	639	\$155.73	\$1,090.10
		1	12' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	100 232	\$169.90	\$169.90
2nd - column (B-2) & (B-3)		2	14' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT		\$198.23	\$396.45
2nd - column (B-5) & (B-1)	0143PBI	2	15' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	250	\$212.39	\$424.77
			Chad Kragness				
	-		TOTAL WEIGHT TH	IS PAGE	8,186		\$15,361.66

QUOTE GOOD FOR 10 DAYS.

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at order, balance upon delivery (unless negotiated otherwise)

SUBTOTAL THIS PAGE \$15,361.66

07/18/2017



## TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



CUSTOMER		FYF-LLC	PO#		REVISED - N			
ATTN:		Ryan Schultz	DATE	•	7/18/2017			
ADDRES	S	43 South Water St East Fort Atkinson, WI 53538	JOB NAM	<u> </u>	The Downtov	*****************	ake Geneva	, WI 53147
PHONE		773-425-6456	JOB LOCA	ATION: E				
FAX				•	<u>X</u>			
TT#		PAGE 3 OF 3		Q0012	<u> </u>	ONDEN_		
ITEM CODE	QTY	DESCRIPTION		RR/FG	WEIGHT	PRICE EACH	TOTAL	
	•							
	1	SUBTOTAL OF PAGE 1			6,068	\$12,428.88	\$12,428.88	
	1	SUBTOTAL OF PAGE 2			8,186	\$15,361.66	\$15,361.66	
		Architectural Grade Beams - Filled, Planed, and	Sanded sm	ooth.				
		Beams marked as "EXT" would be pressure treat	ted before s	staining.				
		Doug Fir beams would be treated with Enviro Sa	afe Plus (see	e attache	ed information	on)		
		All beams would be stained with Hallman Linds.	av - Timber	r Shades	L	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	~~~ <u>~</u>	
		Semin transparent stain	, and the second		Will provide stain color in a couple			
		All beams would be individually paper wrapped.			days.			
		These prices shown are for Architectural Grade Price does not include any hardware.	oeams, squa	are one e				
		Please allow 6-8 weeks production time for these currently.	e beams					
		Chad Kragness						
		TOTAL W	/EIGHT OF	QUOTE	14,254	SUBTOTAL	\$27,790.54	
FREIGHT						\$600.00	_	
QUOTE (	GOOD F	OR 10 DAYS.		TC	OTAL PRICE	FOR QUOTE	\$28,390.51	

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at order, balance upon delivery (unles negotiated otherwise)

APPROVED 07/18/2017