



TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



Final - per Ryan Schultz - 7/17 CUSTOMER FYF-LLC PO# ATTN: Ryan Schultz DATE 7/18/2017 **ADDRESS** 43 South Water St East JOB NAME The Downtowner Fort Atkinson, WI 53538 640 West Main Street, Lake Geneva, WI 53147 JOB LOCATION: **PHONE** 773-425-6456 SHIP MODE FOB LAKE GENEVA, WI FAX QUOTE **ORDER** TT# PAGE 1 OF 3

basement - stair stringers

1st fl - stairs (top of basement stair & bottom of 1st fl stair.)

1st floor - stair stringers

1st floor - along GL E (3-4) & (1-2) & along GL D (2-3)

1st floor - along GL E (2-3)

1st floor - girt-E

1st floor - girt-NE

1st floor - girt-SE 1st floor - girt-NE 1st floor - girt-E 1st floor - girt-N & S

1st floor - along 5 (B-E)

2nd Floor - top of 1st floor stair

2nd Floor - along E (1-2) 2nd Floor - along E (3-5) & along D (2-3)

2nd Floor - along E (3-3) & along D (2-3)

Roof - along E (1-2) Roof - along E (3-5) Roof - along E (2-3) Roof - along 1 (B-E)

2nd - along C (1-2) 2nd - along C (2-3) & (3-5)

ITEM					PRICE	
CODE	QTY	DESCRIPTION	RR/FG	WEIGHT	EACH	TOTAL
	•					
4169PBI	2	17' 3.125 in. x 12.375 in. DF, 24F-1.8E	EXT	454	\$418.38	\$836.76
449PBM	2	5' 3.125 in. x 12.375 in. DF, 24F-1.8E	EXT	144	\$115.80	\$231.60
4199PBI	2	20' 3.125 in. x 12.375 in. DF, 24F-1.8E	EXT	540	\$487.64	\$975.28
6189PBI	3	18' 5.125 in. x 12.375 in. DF, 24F-1.8E	EXT	804	\$512.30	\$1,536.91
6199PBI	1	19' 5.125 in. x 12.375 in. DF, 24F-1.8E	EXT	283	\$540.76	\$540.76
655PBM	. 1	6' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	41	\$116.05	\$116.05
685PBM		8' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	66	\$128.95	\$128.95
6105PBI	1	11' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	92	\$177.30	\$128.93
6155PBI	1	15' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	124	\$241.79	\$241.79
6155PBI	2	16' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	248	\$257.91	\$515.82
		,			* -	,
8229PBI	1	23' 6.75 in. x 12.375 in. DF, 24F-1.8e	EXT	467	\$776.47	\$776.47
4411PBI	1	4' 3.125 in. x 15.125 in. DF, 24F-1.8e	EXT	46	\$111.81	\$111.81
41511PE	1	16' 3.125 in. x 15.125 in. DF, 24F-1.8e	EXT	186	\$419.30	\$419.30
41711PE		18' 3.125 in. x 15.125 in. DF, 24F-1.8e	EXT	394	\$476.48	\$952.95
41911PE	1	19' 3.125 in. x 15.125 in. DF, 24F-1.8e	EXT	220	\$531.11	\$531.11
41513PE	1	15' 3.125 in. x 17.875 in. DF, 24F-1.8e	EXT	205	\$491.16	\$491.16
41713PE	1	18' 3.125 in. x 17.875 in. DF, 24F-1.8e	EXT	233	\$589.39	\$589.39
41913PE	1	19' 3.125 in. x 17.875 in. DF, 24F-1.8e	EXT	260	\$622.13	\$622.13
42713PE	1	27' 3.125 in. x 17.875 in. DF, 24F-1.8e	EXT	370	\$884.08	\$884.08
61511PE	1	15' 5.125 in. x 15.125 in. DF, 24F-1.8e	EXT	273	\$514.49	\$514.49
61711PE	2	18' 5.125 in. x 15.125 in. DF, 24F-1.8e	EXT	618	\$617.39	\$1,234.77
,				210	75700	T - 1 1111
		Chad Kragness				

TOTAL WEIGHT THIS PAGE

SUBTOTAL THIS PAGE

6,068

\$12,428.88

\$12,428.88

QUOTE GOOD FOR 10 DAYS.

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at time of order, balance upon delivery (unless negotiated otherwise)

07/18/2017



TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



			Final - per Ryan Schultz - 7/17
CUSTOMER	FYF-LLC	PO#	
ATTN:	Ryan Schultz	DATE	7/18/2017
ADDRESS	43 South Water St. East	JOB NAME	The Downtowner
	Fort Atkinson, WI 53538	JOB LOCATION:	640 West Main Street, Lake Geneva, WI 53147
PHONE	773-425-6456	000 200/11014.	<i></i>
		SHIP MODE	FOB LAKE GENEVA, WI
FAX		QUOTE	X ORDER
TT#	PAGE 2 OF 3	QUOTE	<u>A</u> ORDER

Γ	ITEM					PRICE	
	CODE	QTY	DESCRIPTION	RR/FG	WEIGHT	EACH	TOTAL
Roof - along 3 (B-E)		1	24' 5.125 in. x 17.875 in. DF, 24F-1.8E	EXT	495	\$988.51	\$988.51
Roof - along 2 (B-E)	62513PE	1	25' 5.125 in. x 17.875 in. DF, 24F-1.8E	EXT	538	\$1,029.70	\$1,029.70
2nd - along 5 (B-E)	82211PE	1	23' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	271	\$959.00	\$959.00
2nd - along 2 (B-E) & along 3 (B-E)		2	26' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	1,240	\$1,084.10	\$2,168.20
2nd - along 1 (B-E)	83011PE	1	30' 6.75 in. x 15.125 in. DF, 24F-1.8E	EXT	744	\$1,250.89	\$1,250.89
(, , , , , , , , , , , , , , , , , , ,							
roof - along 5 (B-E)	82213PE	1	23' 6.75 in. x 17.875 in. DF, 24F-1.8E	EXT	675	\$1,117.40	\$1,117.40
most slave D (4.0)		•					
roof - along B (1-2)		1	15' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	189	\$414.88	\$414.88
roof - along B (3-5)		1	18' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	215	\$497.87	\$497.87
roof - along B (2-3)	41912PE	1	19' 3.125 in. x 16.5 in. DF, 24F-1.8E	INT	240	\$525.53	\$525.53
((2110DF	•	201 5 105 1 10 55 1 DE 04E 1 0E		2.52		Ф7 0 < 1 <
roof - along C (3-5)	62110PE	1	22' 5.125 in. x 13.75 in. DF, 24F-1.8E	EXT	363	\$706.16	\$706.16
roof - along C (1-2)	61510PE	1	15' 5.125 in. x 13.75 in. DF, 24F-1.8E	INT	248	\$414.26	\$414.26
roof - along C (2-3)	61910PE	1	19' 5.125 in. x 13.75 in. DF, 24F-1.8E	INT	314	\$524.73	\$524.73
hacement columns at (F 2) (F 2) (F 2)	(75DD) (01 5 105 '	EV.	174	# 100.05	#20 <i>C</i> 0 <i>C</i>
basement - columns at (E-2), (E-2), (E-3)		3	8' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	174	\$128.95	\$386.86
basement - columns at D-2 & D-3		2	17' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	280	\$274.03	\$548.06
basement - columns at D-1	693PBM	1	18' 5.125 in. x 6.875 in. DF, 24F-1.8E	EXT	150	\$290.15	\$290.15
1st - column (B-1), (B-2), (B-3)	CZEDDM		01 5 105 in a C 075 in DE 04E 1 0E	(NIT	174	C440.07	\$339.82
1st - column (B-3) (B-3)	605DDM	3 1	8' 5.125 in. x 6.875 in. DF, 24F-1.8E 9' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT INT	174 74	\$113.27 \$127.44	\$127.44
the control of the co	6105PBI	7	10' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	581	\$127.44	\$990.98
<u> </u>	6105PBI	7	11' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	639	\$155.73	\$1,090.10
2nd - column (C-5)	61/5DD1	1	12' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	100	\$169.90	\$169.90
2nd - column (B-2) & (B-3)		2	14' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	232	\$198.23	\$396.45
2nd - column (B-5) & (B-1)		2	15' 5.125 in. x 6.875 in. DF, 24F-1.8E	INT	250	\$212.39	\$424.77
211a Column (D-0) & (D-1)	0170101		15 5.125 m. A 0.075 m. DI , 241-1.0E	11111	230	Ψ212.39	ψ+∠+.//
ŀ			Chad Kragness				
_			TOTAL WEIGHT TH	IS PAGE	8,186		\$15,361.66

QUOTE GOOD FOR 10 DAYS.

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at order, balance upon delivery (unless negotiated otherwise)

07/18/2017

SUBTOTAL THIS PAGE



TIMBER TECHNOLOGIES L.L.C.

106 Bremer Avenue~ Colfax, WI 54730 Phone: 715-962-424 2~ Fax: 715-962-4193



CUSTOM	1ER	FYF-LLC	PO#		REVISED - N	NO FABRICAT	ION	
ATTN:		Ryan Schultz	DATE	•	7/18/2017			
ADDRES	S	43 South Water St East Fort Atkinson, WI 53538	JOB NAM	<u> </u>	The Downtov	***************************************	ake Geneva	, WI 53147
PHONE		773-425-6456	JOB LOCA	ATION: E				
FAX				•	<u>X</u>			
TT#		PAGE 3 OF 3		Q0012	<u> </u>	ONDEN_		
ITEM CODE	QTY	DESCRIPTION		RR/FG	WEIGHT	PRICE EACH	TOTAL	
	•							
	1	SUBTOTAL OF PAGE 1			6,068	\$12,428.88	\$12,428.88	
	1	SUBTOTAL OF PAGE 2			8,186	\$15,361.66	\$15,361.66	
		Architectural Grade Beams - Filled, Planed, and	Sanded sm	ooth.				
		Beams marked as "EXT" would be pressure treat	ted before s	staining.				
		Doug Fir beams would be treated with Enviro Sa	afe Plus (see	e attache	ed information	on)		
		All beams would be stained with Hallman Linds.	av - Timber	r Shades	L	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	~~~ <u>~</u>	
		Semin transparent stain	J		Will provide stain color in a couple			
		All beams would be individually paper wrapped.						
		These prices shown are for Architectural Grade Price does not include any hardware.	oeams, squa	are one e				
		Please allow 6-8 weeks production time for these currently.	e beams					
		Chad Kragness						
		TOTAL W	/EIGHT OF	QUOTE	14,254	SUBTOTAL	\$27,790.54	
FREIGHT \$600.00						_		
QUOTE (GOOD F	OR 10 DAYS.		TC	OTAL PRICE	FOR QUOTE	\$28,390.51	

PLEASE VERIFY LENGTHS AND QUANTITIES BEFORE ORDERING.

TERMS: half down at order, balance upon delivery (unles negotiated otherwise)

APPROVED 07/18/2017